

KAGRA's situation

Mar. 2015: iKAGRA run (Simple Michelson Interferometer)

- There was no calibration group.
- Some site people worked on calibration and reconstruction.

May. 2018: bKAGRA phase-1 run (Cryogenic MI)

- Only online $h(t)$ was provided.
- There were no photon calibrator (Pcal).



Now: Commissioning test


- We start to work on reconstructing the displacement of each DOF.
- Pcal installation is ongoing.

Dec. 2019: Join the O3 observation (DRFPMI)


- Two Pcal will be ready.
- Online, low-latency, and offline $h(t)$ will be provided.

CAL activities during previous operation

- We measured the optical gain (C) response by Free-Swinging method.
~15% uncertainty in estimated optical gain.
- OLTF (G) was measured by the digital control system.
- Actuator efficiency (A) was estimated by G/C



3



Our mission on O3

Pcal instrument

- Calibration of the laser power with KAGRA's working standard.
- Monitoring beam positions of Pcal laser.

IFO instrument


- Measurement of the optical response with pcal.
- Independent measurement of the time dependent coefficients of the optical plant (C) and the actuation plant (A)

Software


- Providing low-latency and offline $h(t)$
 - Correcting time dependent coefficient.
 - Precise $h(t)$ generation with FIR filters
- Providing information of the systematics and uncertainty of the reconstructed strain signal.

KAGRA Calibration instruments



Gravity Field Calibrator



Photon Calibrator



Actuation method
-Photon pressure
-Gravity field gradient



pcal installation

Both X- and Y-Pcal had been installed in last year.

We started to measure

- the accuracy of the beam position
- optical loss between Tx and Rx modules



JGW-D1807705



Optical efficiency

model


$$P = (P_{Tx} + P_{Rx}) / 2$$
$$P = e_{Tx} P_{Tx}$$
$$P = e_{Rx}^{-1} P_{Rx}$$
$$x = \frac{2P \cos \theta}{c} s(\omega)$$

h(t) reconstruction scheme

JGW-G1707452

$$\frac{1 + G}{C} = \frac{v_{err}}{x_{pcal}}$$

Pcal helps us for monitoring fluctuations of A and C gain individually.



$h(t)$ can be generated using simple filter.

$$\frac{1 + G}{AC} = \frac{v_{err}}{x_{ctrl}}$$

$$G = \frac{x_{in2}}{x_{in1}}$$


We can monitor the gain fluctuation of G .
Which is a cause of gain fluctuation, A or C ?

$h(t)$ reconstruction pipeline (Calibration software)

- Digital control and DAQ systems on KAGRA are the copy of LIGO's systems.
- We also use a LIGO system as a part of data transfer system.

- So the framework of `gstlal` can be used easily.

LIGO's
control software



Reconstruction pipeline

Online $h(t)$ on digital control system

- Main user: commissioners
- Filter process: full IIR
- Delay: within 1s




Low-latency $h(t)$ on gstlal-calibraion

- Main user: data analysis
- Filter process: IIR + FIR
- Delay: $\sim 4s$


Offline $h(t)$ on gstlal-calibraion

- Main user: data analysis
- Filter process: full FIR
- Delay: in discussion

phase-1 run monitors



Online $h(t)$ by real-time model + Low-latency/Offline $h(t)$ by gstlal-calibraion




KAGRA CAL Subway map


KAGRA Subway map ver.0

JGW-E1809550


Pcal



DARM





Reconstruction




K1_CAL_GDS_Strain

MCL reconstruction



MCL reconstruction



The time delay in the AOM path, τ_C , can be ignored.

The total delay in the SUS path can be approximated as 6 clocks in 16kHz sampling because $\tau_C + \tau_{AOM} + \tau_{SUS} \ll 61us$ (I hope).

The gstlal-calibration receives the signals before applying time delay.

$\Delta f'$ is 165us ($= \tau_{IPC} + \tau_{dAA} + \tau_{ADC} + \tau_{aAA} + \tau_C$) behind from true time.

Summary

Pcal installation is already finished.

Characterization of Pcal instrument is ongoing

- Stability of laser power

- Measurement of the optical loss

- Precision of the beam position

We are now developing the reconstruction pipeline of $h(t)$

- First pipeline test are planned during Commissioning test.

- Data transfer test had been already succeeded.